


EuroPHit


D3.4_PHPP Result Sheets

DRAFT

CS05 Courcelles-Lès-Lens

Social Apartment building

SIA Habitat Courcelles-Lès-Lens

INTELLIGENT ENERGY – EUROPE II

Energy efficiency and renewable energy in buildings

IEE/12/070

EuroPHit

[Improving the energy performance of step-by-step refurbishment and integration of renewable energies]

Contract N°: SI2.645928



Co-funded by the Intelligent Energy Europe
Programme of the European Union

Technical References

Project Acronym	EuroPHit
Project Title	Improving the energy performance of step-by-step refurbishment and integration of renewable energies
Project Coordinator	Jan Steiger Passive House Institute, Dr. Wolfgang Feist Rheinstrasse 44/46 D 64283 Darmstadt jan.steiger@passiv.de
Project Duration	1 April 2013 – 31 March 2016 (36 Months)

Deliverable No.	D3.4
Dissemination Level	PU
Work Package	WP3_Practical Implementation
Lead beneficiary	04_MosArt
Contributing beneficiary(ies)	03_LAMP
Author(s)	Simon CAMAL
Co-author(s)	
Date	10 10 2014
File Name	EuroPHit_D3.4_20141010_LAMP_CS05_PHPP_ResultSheet.doc

The sole responsibility for the content of this [webpage, publication etc.] lies with the authors. It does not necessarily reflect the opinion of the European Union. Neither the EACI nor the European Commission are responsible for any use that may be made of the information contained therein.

Table of Contents

Abstract	4
1 Existing building: PHPP Result Sheet	5
1.1 PHPP Result sheet of the existing building	5
2 Retrofit steps	6
2.1 Overall refurbishment Plan	6
2.1.1 Retrofit steps:	6
2.1.2 Efficiency Improvements	7
3 Completion of step-by-step refurbishment to EnerPHit	8
3.1 PHPP Result Sheet of the completed EnerPHit standard	8

List of tables and figures

Figure 1: Specific energy efficiency values of the existing building modelled with PHPP 9 Beta	5
Figure 2: Overview refurbishment steps	6
Figure 3: Overview energy efficiency improvement according to the overall refurbishment plan	7
Figure 4: Specific energy efficiency values of the completed project modelled with PHPP 9 Beta	8

Abstract

This document provides a short overview of the efficiency improvement of a step-by-step refurbishment to EnerPHit standard to be undertaken for the project Courcelles.

First, the result sheet of the project's current status will present the calculated energy consumption of the existing building.

The PHPP result sheet of the completed EnerPHit retrofit will present the energy demand estimated for the completion of the project according to the overall refurbishment plan



1 Existing building: PHPP Result Sheet

1.1 PHPP Result sheet of the existing building


EnerPHit verification			
		Building	Courcelles Blanc Nes / Gris Nes
		Street	Rue de Boulogne
Architecture:		Mechanical System:	
Street:		Street:	
Postcode/City:		Postcode/City:	
Energy consulting:		Certification:	
Street:		Street:	
Postcode/City:		Postcode/City:	
Year of Construction:	2015	Interior temperature winter [C°]	20,0
Number of dwelling units:	16	Interior temp. summer [C°]	25,0
Number of Occupants:	34,4	Internal heat gains winter [W/m²]	2,1
Exterior vol. V _e :	3700,0 m³	Internal heat gains summer [W/m²]	5,6
		Spec. capacity [Wh/K per m² TRA]	204
		Mechanical cooling:	
Specific building demands with reference to the treated floor area			
	Treated floor area	1203,1 m²	
Space heating	Annual heating demand	113 kWh/(m².a)	25 kWh/(m².a)
	Heating load	48 W/m²	-
	Overall specific space cooling demand	kWh/(m².a)	-
Space cooling	Cooling load	W/m²	-
	Frequency of overheating (> 25 °C)	0,0 %	-
Primary Energy	heating, cooling, dehumidifying, DHW	450 kWh/(m².a)	237 kWh/(m².a)
	DHW, space heating and auxiliary electricity	385 kWh/(m².a)	-
Specific primary energy reduction through solar electricity	kWh/(m².a)	-	-
Airtightness	Pressurization test result n ₅₀	5,0 1/h	1 1/h
EnerPHit (retrofit): building characteristic values			
Building envelope	Exterior insulation to ambient air	0,39 W/(m².K)	-
Average U-values	Exterior insulation underground	W/(m².K)	-
	Interior insulation to ambient air	W/(m².K)	-
	Interior insulation underground	3,33 W/(m².K)	-
	Thermal bridges ΔU	0,04 W/(m².K)	-
Windows	External doors	2,88 W/(m².K)	-
	External doors	2,50 W/(m².K)	-
Ventilation system	Effective heat recovery efficiency	0 %	-

Figure 1: Specific energy efficiency values of the existing building modelled with PHPP 9 Beta

2 Retrofit steps

2.1 Overall refurbishment Plan

2.1.1 Retrofit steps:

The first step is chosen as to create the largest energy reduction upfront: airtightness + MVHR can reduce by 60% the heating demand.

Step	Year	Measure	Specific Heating Demand	Specific Primary Energy Demand	Additional Specific Renewable Energy Gains
0	2013	Existing Building	113	450	0
1	2015	Airtightness + MVHR	59	291	0
2	2015	Windows	41	246	0
3	2016	External walls	30	219	0
4	2018	Roofs + Efficient DHW + Solar Thermal + Lighting	22	137	15
5	2019	Slab	13	119	15
6	2021	40 kWp PV	13	119	15+82 (thermal+PV)

Figure 2: Overview refurbishment steps

2.1.2 Efficiency Improvements




Figure 3: Overview energy efficiency improvement according to the overall refurbishment plan

3 Completion of step-by-step refurbishment to EnerPHit

3.1 PHPP Result Sheet of the completed EnerPHit standard


EnerPHit verification				
		Building	Courcelles Blanc Nes / Gris Nes	
		Street	Rue de Boulogne	
Architecture: Street: Postcode/City:		Postcode/City	Courcelles les Lens	
		Country	France	
Energy consulting: Street: Postcode/City:		Building type	MFH	
		Climate	Lille	
Year of construction: 2015 Number of dwelling units: 16 Number of occupants: 34.4 Exterior vol. V _e : 3700.0 m ³		Attitude of building site (in m) above sea level	24	
		Home owner/client	SIA Habitat	
Mechanical system: Street: Postcode/City:		Street	67 Avenue des Potiers	
		Postcode/City	59506 Douai	
Certification: Street: Postcode/City:		Street		
		Postcode/City		
Interior temperature winter [C°]		20.0	Interior temp. summer [C°]	25.0
Internal heat gains winter [W/m²]		2.1	IHG summer [W/m²]	3.6
			Spec. capacity [Wh/K per m² TFA]	204
			Mechanical cooling	
Specific building demands with reference to the treated floor area				
	Treated floor area	1203,1	m²	
Space heating	Annual heating demand	13	kWh/(m²a)	25 kWh/(m²a)
	Heating load	9	W/m²	-
	Overall specific space cooling demand		kWh/(m²a)	-
Space cooling	Cooling load		W/m²	-
	Frequency of overheating (> 25 °C)	0,1	%	-
Primary Energy	heating, cooling, dehumidifying, DHW	119	kWh/(m²a)	120 kWh/(m²a)
	DHW, space heating and auxiliary electricity	61	kWh/(m²a)	-
	Specific primary energy reduction through solar electricity	82	kWh/(m²a)	-
Airtightness	Pressurization test result n50	0,6	1/h	1.1/h
EnerPHit (retrofit): building characteristic values				
Building envelope	Exterior insulation to ambient air	0,11	W/(m²K)	-
Average U-values	Exterior insulation underground		W/(m²K)	-
	Interior insulation to ambient air		W/(m²K)	-
	Interior insulation underground	0,20	W/(m²K)	-
	Thermal bridges ΔU	0,02	W/(m²K)	-
Windows	Windows	0,94	W/(m²K)	-
	External doors	2,50	W/(m²K)	-
Ventilation system	Effective heat recovery efficiency	76	%	-

Figure 4: Specific energy efficiency values of the completed project modelled with PHPP 9 Beta